

25 Series

Indoor Building Entrance Terminal


CPE/Premise Wiring

Headend/CO

MDU

Utility/Municipality

Wireless



25050-110-M110PC

At the point of demarcation, Building Entrance Terminals (BETs), safeguard communication equipment from damaging electrical surges that may get onto incoming lines. Tii's low profile 25 Series BETs do not have a splice chamber.

KEY PRODUCT BENEFITS

- ▶ Available in 25, 50 and 100 pair counts
- ▶ Terminations: 66 in/out; 110 in/out
- ▶ Industry standard 5-pin protector field sealed to protect from moisture and corrosion
- ▶ Available with gas tube module 175-3C1EW-NL factory installed
- ▶ Compact footprint
- ▶ Steel construction
- ▶ Manufactured from 18 gauge, epoxy powder coated steel

INDUSTRY STANDARDS

- ▶ UL 497 Listed for primary and secondary protection
- ▶ Telcordia GR-937/GR-2916



Tii Technologies Inc.

Corporate Headquarters:

141 Rodeo Drive
Edgewood, NY 11717


Phone: 631.789.5000

Fax: 631.789.5063

Toll Free: 888.844.4720

sales@tiitech.com

25 Series BETs



Dimensions are in Inches

ORDERING INFORMATION

Model No.	Pair Count	Input	Output	Protectors Installed	Cover
25025-110-M110C	25	110	110	No	Yes
25025-110-M110PC	25	110	110	Yes	Yes
25025-66-M66C	25	66	66	No	Yes
25025-66-M66PC	25	66	66	Yes	Yes
25050-110-M110C	50	110	110	No	Yes
25050-110-M110PC	50	110	110	Yes	Yes
25050-66-M66C	50	66	66	No	Yes
25050-66-M66PC	50	66	66	Yes	Yes
25100-110-M110C	100	110	110	No	Yes
25100-110-M110PC	100	110	110	Yes	Yes
25100-66-M66C	100	66	66	No	Yes
25100-66-M66PC	100	66	66	Yes	Yes

Units with protectors installed have Model # 175-3C1EW-NL